



ZESTAWIENIE STALI									
Obiekt:		Jawornik						23 września 2020	
Nr rys:			Treść:						
Element	Pozycja	Liczba	Przedmiot	Długość	Ciężar			Materiał	Uwagi
					Jedn.	Szt.	Całk.		
		[szt]		[mm]	[kg/m]	[kg]	[kg]		
Jawornik	1	1	HEB160	2000	42.60	85.20	85.20	S235	
	2	1	HEB160	2300	42.60	97.98	97.98	S235	
	3	2	HEB200	5010	61.30	307.11	614.23	S235	
	4	1	HEB220	6860	71.50	490.49	490.49	S235	
	5	1	IPE200	2865	22.40	64.18	64.18	S235	
					Ciężar 1 element [kg]		1352.07		
Wykonać		1				Ciężar sumaryczny [kg]		1352.07	
					Ciężar całkowity [kg]		1352.07		
					Naddatek na spoiny [kg]		10.00%	135.21	
					Naddatek na elementy dodatkowe [kg]		10.00%	135.21	
					Ogółem [kg]		1622.49		